PACBRIDGE

PacBridge Installation Sequence

Part I – Footings and Abutment Walls


Modular Abutment Installation

- Place abutment footing units level and at proper elevations
- Stock abutment units plumb onto center of footings

Part II – Component Placement

Complete all stream restoration work

- Place modular deck units
- Install hardware package
- Install guardrail (if applicable)
- Complete roadway work



General Specifications


Design Data	
Design Criteria	AASHTO LRFD U80, L90, HL93 or HS20/25
Available Guard Rails	Crash Ratings 1 & 2

Design details shall be in accordance with a Licensed Professional Engineer in the state of installation.

QUALITY CONTROL

Concrete cylinder compression testing is performed on every concrete batch by a third party testing agency. Although ACI certified, we elect to provide Project Owners with fully transparent test results.





Spread Footing - 15"x30"x7.5'

If required for low bearing capacity soils, the first abutment row can use spread footing blocks. These can also be incorporated under the wing walls as necessary.

Additional Sizes Available: Thickness - 8" Width - 3'-5' (0.5' increments) Length - up to 25'

A Service Disabled Veteraned Owned Small Business

Additional Size Available: 30"x30"x90"

